



अधीक्षण अभियंता का कार्यालय
OFFICE OF THE SUPERINTENDING ENGINEER
कार्य स्थापना अनुभाग, WORKS ESTABLISHMENT SECTION
राष्ट्रीय प्रौद्योगिकी संस्थान कर्नाटक, सुरतकल

NATIONAL INSTITUTE OF TECHNOLOGY KARNATAKA, SURATHKAL

पोस्ट श्रीनिवासनगर, मंगलूर - 575025, कर्नाटक, भारत. / Post Srinivasnagar, Mangaluru - 575025, Karnataka, INDIA.

Phone: [0824] - 2473029, 2473028

Email: se@nitk.edu.in

Website: <http://www.nitk.ac.in>

No.SE/Elect/2026-27/Tech(mech)-1A/

Date: 17-07-2026

BRIEF TENDER NOTIFICATION

Sealed tenders on percentage basis are hereby invited from the registered civil contractors of KPWD / CPWD etc., on behalf of the Director, National Institute of Technology Karnataka Surathkal for the work noted below. The tenders shall be received in this office on **24-07-2026 up to 10:00AM**. The tenders will be opened on the same day by the undersigned if possible.

Sl. No.	Name of the works	Estimate amount put to tender (Rs.) (Including GST)	E.M.D
1.	Interconnection of water supply line from Shivalika hostel to Thrishul hostel in NITK	1,78,214.00	In the form of bid Security Declaration

Eligibility Class of Contractor:

Civil: Karnataka PWD class IV or above / Central PWD class V or above

Terms and Conditions:

1. The tendering bidder must submit a 'Bid Security Declaration' in the case of NSIC/MSME/ Startups bidders seeking exemption from EMD/Bid Security, they should be attaching then SIC/MSME/ Startups certificate (obtained for relevant NIC & Activity), otherwise Bid Security Declaration must be submitted.
2. The tender receiving after due date will be rejected.
3. Envelope super scripted as name of the work and due date and addressed to as 'The Superintending Engineer, NITK Surathkal, Post Srinivasnagar, Mangaluru - 575 025' be sent so as to reach this office on or before the due date mentioned.
4. The tentative Bill of Quantities (BOQ) for the work is enclosed. The intending contractor shall quote a **single percentage** rate, either above, below or at par with the total amount of the approved estimate, on the firm's letterhead.
5. The contractor must submit the copy of valid registered certificates of PWD license, EPF, ESI, and GST & PAN
6. The Contractor must visit the site and analyze the nature of work before submitting the tender quotation.
7. The work shall be completed within 25 days from the date of issue of the work order. In case of delay, a penalty at the rate of 1% of the work order value per week, shall be levied.
8. If the successful bidder (L1) fails to commence the work or refuses to execute the work after issue of the work order without valid justification acceptable to the Institute, the Institute reserves the right to cancel the work order and blacklist/debar the contractor from participating in any quotation/tender process of the Institute for a period of up to three (3) years.
9. The contractor shall commence the work from the date of issue of the Work Order.
10. The contractor shall submit a detailed work schedule/programme to the SE Office within 7 days from the date of issue of the Work Order for review and record.
11. The contractor shall maintain a stage-wise approval register for obtaining the signatures of the competent authority at various stages of the work, as directed by the Engineer-in-Charge, prior to execution of the respective activities. Failure to obtain the required approvals or to maintain the register shall be treated as a

serious violation of the contract conditions and may result in cancellation of the work at the contractor & risk and cost, without entitlement to any claim arising therefrom.

12. The Contractor shall provide a valid official e-mail ID for all official communications.

13. Security Deposit at the rate of 5% of the work value shall be deducted from the contractor's bill. The amount may be claimed after six months from the date of satisfactory completion of the work.

14. The undersigned reserve the right of rejecting all the tenders without assigning any reasons thereof.



Superintending Engineer

अधीक्षक अभियंता NITK Surathkal Engineering

कार्य स्थापना अनुभाग / Works Establishment Section

राष्ट्रीय प्रौद्योगिकी संस्थान कर्नाटक, सुराठकल

National Institute of Technology Karnataka, Surathkal

पोस्ट श्रीनिवासनगर - ५७५ ०२५ / Post Srinivasnagar - 575 025



Si No:	Details of work	Quantity	UOM
1	Excavating trenches by mechanical / manual means of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, for all depth, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m : Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia	2.84	Cum
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (including equivalent design mix)	0.47	Cum
3	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply and all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. 40 mm nominal dia Pipes	211.05	Meter
4	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland / Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge, for the following grades of concrete.: Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement. Concrete of M25 grade with minimum cement content of 330 kg /cum	0.47	Cum

R. N. S.

अधीक्षक अभियंता / Superintending Engineer
 कार्य स्थापना अनुभाग / Works Establishment Section
 राष्ट्रीय प्रौद्योगिकी संस्थान कर्नाटक, सुरथिकल
 National Institute of Technology Karnataka, Surathkal
 पोस्ट श्रीनिवासनगर, - ५७५ ०२५ / Post Srinivasnagar - 575 025